

**Name of work; Providing Rain water harvesting facilities in ward no; 14 Bagalagunte
T.Dasarahalli Sub Division**

Sl.No	Description of Work	Unit	Quantity	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the Engineer in charge of the work	Cum	32.25	130.00	one hundred and thirty rupees only
EIRL-1	KSRB 2-1.2 Earth work in surface excavation in hard soil for levelling and lowering the ground manually other than the foundation of buildings, culverts, road drains and trenches of pipe lines and cables and removing the excavated stuff to a distance not exceeding 50 mtrs and lift up to 105 mtrs excavated surface levelled after breaking of clods and neatly dressed disposed earth to be levelled after breaking of clods and neatly dressed as per specifications No KBS 2.1 (A) / 2.3.1 P-5, I-2.2 PWD SR 2018-19	Cum	47.25	244.84	two hundred and fourtyfour rupees and eighty four paisa only
EIRL-2	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (KPWD SR 2018-19, Page No.13, Item No.4.2)	Cum	23.63	5615.66	five thousand six hundred and fifteen rupees and sixty six paisa only
EIRL-3	KRSB 4-1.5; Providing and laying in position plain cement concrete of mix M20 with OPC Cement @ 300 kgs with 20 mm and down size graded granite metal coarse aggregate @0.64 cum and fine aggregate @ 0.43 cum with super plastisicer @ 3 ltr conforming to IS 9103 -1999 Reaffirmed -52008 machine mixed concrete laid in layers not exceeding 15 cms thick well compacted in foundation and plinth and cills including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications No; KBS 4.1, 4.2 (P-12, I-4.5 PWD SR 2018-19)	Cum	21.17	6167.66	six thousand one hundred sixty seven and sixty six paisa only

RL-4	Providing and fixing granite benches including cost of materials labours as per specifications (Data Rate Approved)	Nos	42.00	11076.45	eleven thousand seventy six and fourty five paisa only
L-5	KSRB 4-6.4 Providing and removing centering and shuttering strutting propping etc and removal of form work for vertical surface such as walls at any thickness including attached plasters ,buttresses plinth,cills and string courses including cost of materials labours as per specifications specification No;KBS 4.6.2 P-16, I-4.31 PWD SR 2018-19	Sqm	95.76	398.42	three hundred ninty eight rupees and fourty two paisa only
L-6	Providing 20 mm thick cement plaster in single coat with cement mortar 1;4 to stone masonry and concrete surface including rounding off corners wherever required smooth rendering and removing scaffolding including cost of materials labour curing complete as per specifications	Sqm	204.96	301.59	three hundred one rupees and fifty nine paisa only


Signature of the Contractor


Executive Engineer
Basarahalli Division